Estimate of the approximate quantities for constructing Drains at Chamarajnagar Town.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
1	Constructing 3″ section semi-peg top drain with cement concrete in the proportion of 1 : 2 : 4 at bed and sides and cement plastering the exposed surface including earth work, etc. complete as per design	R.ft.	..	6,590	
2	Repairing the existing slab drain by removing and resetting 30 per cent of slabs and providing cement concrete $1\frac{1}{2}' \times \frac{3}{4}' \times \frac{1}{4}'$ at joints including excavation and providing baby jelly cement concrete for bottom portion $\frac{1}{4}' \times \frac{1}{8}'$ and cement pointing joints, etc. complete ..	R.ft.	..	500	
3	Repairing the existing box drain by forming U shaped drain at the centre with about 3″ thick cement concrete in the proportion of 1 : 2 : 4 over 3″ thick lime concrete bed and the surface plastered over by $\frac{1}{2}$″ cement plastering in the proportion of 1 : 3	R.ft.	..	350	

N. KRISHNIENGAR,
Sanitary Engineer.

WATER SUPPLY DIVISION.

Notification dated 9th February 1938.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Water Supply Division, up to 26th February 1938, for excavating, removing, cleaning, carting and stacking 15″ steel pipes from the "Y" Tank main to Combined Jewell Filters. An approximate estimate of quantities for each building is given below. These quantities are not guaranteed. The work should be completed by the end of April 1938.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office Water Supply Division, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 275, in cash or Government, Promissory Notes, as earnest money, and be superscribed "Tender for excavating, removing, carting and stacking 15″ steel pipes from the "Y" Tank to Combined Jewell Filters" in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than the estimated rate will not be accepted.

Removing 15″ steel pipes from the "Y" Tank main and carting them to C. J. F.

No.	Items of work	Unit	Rate	Quantity	Cost
			Rs. a. p.		Rs.
	Labour:				
1	Earthwork excavation and refilling with consolidation, etc. in all soils	C.yd.	0 0 3	9,350	
2	Removing, cleaning 15″ steel pipes 18 feet long, specials, lead jointings, etc.*	Cwt.	0 2 6	8,000	
3	Carting the 15″ pipes from the work spot to C. J. F. average distance 10 miles including stacking as per instructions	Cwt per mile.	0 0 6	80,000	

*About 10 lead jointings shall be melted to separate the lead and weighed in the presence of the Executive Engineer or his authorised agent who will fix the average weight of lead per joint, according to this weight per joint the contractor shall return the removed lead to the stores in the form of bricks.

The contractor will be held responsible for all damages to pipes during the transit or at the time of removing, etc.

V. GANESHA IYER,
Executive Engineer.

BUILDINGS DIVISION, BANGALORE.

Notification dated 28th January 1938.

A number of sites admirably suited for business premises, bungalows and cottages have been formed on the grounds of the old Mental Hospital on the Kempe Gowda Road, Bangalore City, situated in the heart of the City and in the midst of business locality of the town and they will be sold by public auction on Saturday the 26th February 1938, between 8-30 A.M. and 11 A.M. Details of the sites can be had at the Office of the Executive Engineer, Buildings Division, on any working day between 3 P.M. and 5 P.M.

Intending bidders must first deposit Rs. 50 at the commencement of the bid. In the case of the successful bidder, it will be adjusted towards the bid value. In the case of unsuccessful bidders, the amount will be returned to them at the end of the sale the same day. The site or sites will be knocked down to the highest bidder who has to deposit immediately 50 per cent of the bid amount and the balance in three days time.

The site or sites sold will be handed over after full payment of the bid value.

The confirmation of the sale rests with the Government.

Abstract Notification dated the 4th February 1938.

The attention of the public is hereby invited to the detailed notification calling for tenders for constructing a Police Station at Ooparpet, Bangalore City, published in pages 186-187, Part VI of *Mysore Gazette*, dated 10th February 1938.

The last date for the receipt of the tender is 25th February 1938.

B. R. GARUDACHAR,
Executive Engineer.

KOLAR DIVISION.

Notification dated 10th February 1938.

1. Sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 12 NOON on 5th March 1938, for constructing a Grainage Building at Talaganara in Chintamani Taluk.

2. Tenders in the prescribed form obtainable from the Office of the Executive Engineer, Kolar Division, should be addressed to the Executive Engineer, Kolar Division, in a sealed cover and